BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

SCHEDULE-B

Name of Work: **Reserve fund for emergency work in Dasarahalli Ward No.15**

(Improvements and Construction of Cement Concrete road & RCC culverts at Coconut garden passages in Dasarahalli Ward No.15)

Sl. No	Description of work	Unit	Qty	Sanctioned Approved Rates	
				In Figures	In Words (Rs.)
1	2	3	4	5	6
1	Earthwork excavation by manual means in hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed the disposed earth to be leveled neatly after breaking of clods Complete as per specifications.	Cum	371.25	90.72	Rupees Ninety and Seventy Two Paise Only
2	Plain cement concrete M10 MIx with crushed stone aggregates 40m nominal size mechanically mixed, placed in foundation and compacted by vibration including curing for 14days Complete as per specifications.	Cum	75.64	3997.08	Rupees Three Thousand Nine Hundred Ninety Seven and Eight Paise Only
3	Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete (RMC) for R.C.C works laid in 15cms thick layers and well compacted vibrating curing and necessary steel or ply wood or plank centering and form work etc., including smooth finish in CM 1:3,with all lead and lift etc., Complete as per specifications.	Cum	127.23	6348.34	Rupees Six Thousand Three Hundred Forty Eight and Thirty Four Paise Only
4	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery Complete as per specifications.	q	63.62	7244.04	Rupees Seven Thousand Two Hundred Forty Four and Four Paise Only
5	Providing and removing centering, shuttering, strutting, propping etc., for columns, pillars, piers, abutments, post and struts, square / rectangular / polygon in plan including cost of all materials, labour Complete as per specifications.	Sqm	324.60	330.72	Rupees Three Hundred Thirty and Seventy Two Paise Only
6	Supplying and fixing precast rainforced concee slab 10cm thick including cost of reinforcement as per design and drawing material cost, transportation, hire charges of machinery, machine cutting the vertical face to get plain even surface stc., complete with all leads and lift conveyance charges, labour charges inclusive of cost of all materials. Complete as per specifications.	Sqm	77.33	1600.00	Rupees One Thousand Six Hundred Only

Signature of the Contractor

EXECUTIVE ENGINEER
KRIDL, BBMP, Bangalore

Executive Engineer

7	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading Complete as per specifications.	Cum	371.25	78.24	Rupees Seventy Eight and Twenty Three Paise Only

Note: The said work for sanctioned estimate cost Rs.20.00 Lakhs (Rupees Twenty Lakhs Only) (Incl.10%+1%KRIDL Charges + 1% Quality control tests Charges) based On "Approved SR Rates"

Signature of the Contractor

EXECUTIVE ENGINEER
KRIDL, BBMP, Bangalore

Executive Engineer,
Dasarahalli Division,